

Performance Requirement Summary (PRS)

Maintain the Clark River Channel

3.1 Make the river navigable

Task	Standards	Incentive/Remedy
<p>3.1.1 The contractor shall establish and maintain depth of channel for Clark River.</p>	<p>STD: 12 feet deep, mean low water</p> <p>AQL: Any location less than 12 feet deep cannot exceed 4 linear feet perpendicular to the channel. No more than 4 occurrences of this per mile.</p> <p>STD: 12 feet deep, mean low water</p> <p>AQL: No points with depth less than 11 feet</p>	<p>Failure to meet standard will be a deduction of \$100 per incident. Any points less than 10 feet will be a deduction of \$300.</p> <p>Any groundings (of compliant craft) in the Channel shall be a deduction of \$1,000.</p>
<p>3.1.2 The contractor shall collect, manage, and dispose of dredged materials for Clark River.</p>	<p>STD: Compliant with federal, state, EPA, and local laws and regulations</p> <p>AQL: 100%</p> <p>STD: Any non-compliant incidents shall be immediately remediated.</p> <p>AQL: Remediation begun within 24 hours 100% of the time</p>	<p>Contractor is responsible for cleanup costs associated with handling materials in a manner that is not compliant with regulations.</p>
<p>3.1.3 The contractor shall establish and maintain width of channel for Clark River.</p>	<p>STD: 100 feet wide</p> <p>AQL: 90% of channel \geq 100 ft</p> <p>STD: 100 feet wide</p> <p>AQL: Any bottlenecks in river (less than 100 feet shore to shore) shall have the channel within 10 feet of each shore line.</p> <p>STD: 100 feet wide</p> <p>AQL: No points less than 80 feet</p>	

Performance Requirement Summary (PRS)

3.2 Identify the navigation channel

Task	Standards	Incentive/Remedy
<p>3.2.1 The contractor shall maintain channel markers for Clark River.</p>	<p>STD: Identifying information (color, numbers, letters, shape, etc) must be clearly visible</p> <p>AQL: All color discernible at 1/4 mile. 95% of all lettering/numbering legible at 200 yards</p> <p>STD: Displaced markers / buoys replaced within 24 hours of detection</p> <p>AQL: Additional time allowed for unsafe weather conditions</p>	
<p>3.2.2 The contractor shall mark channel for Clark River.</p>	<p>STD: Compliant with USCG Navigation rules</p> <p>AQL: 100%</p> <p>STD: Visible</p> <p>AQL: Visible within 1/4 mile during normal weather conditions</p> <p>STD: Execute on a variety of platforms [Specify]</p> <p>AQL: Execute on a variety of platforms [Specify]</p> <p>STD: Within 10 feet of channel edge</p> <p>AQL: None greater than 15 feet 90% of all buoys are within the standard</p>	

3.3 Update the navigation charts

Task	Standards	Incentive/Remedy
<p>3.3.1 The contractor shall update current navigation charts for Clark River.</p>		